



MECHANICAL DEMOLITION

Lakota Solids Systems Improvements

Federal Way, WA

PROJECT

Ascendent was contracted to remove the floating lid cover on one of the holding tanks attached to the digester building. The lid was constructed of steel, and had a ring of concrete ballast blocks leading to a total weight of 125,000 Lbs. After the tank had been made inert with nitrogen gas and existing solids pumped down, Ascendent prepped, rigged and removed the lid over the course of 5 days. The lid was removed as singular piece and fully recycled.

ACHIEVEMENT

The Tank Lid was removed safely and without incident, on time and as scheduled.



OUR CRUCIAL SKILLSETS

Time/Schedule Management • Complex Logistical Planning • Safety Record/Protocols